

23/08/2016

Michael Boland
Executive Scientist
Water and Environmental Services
Wicklow Country Council
County Buildings
Wicklow Town
Co. Wicklow

RE: Section 55 Monitoring Data, Ballinclare Quarry – Air Monitoring and Dust Monitoring Update

Dear Mr. Boland,

As required by the recent section 55 notice (dated 3rd June 2016), issued to Kilsaran International, I am writing to you to provide an update on the air and dust monitoring at Ballinclare Quarry.

1. Overview of air monitoring programme to date

In accordance with the previously outlined monitoring programme from the letter dated 20th June 2016, air sampling was undertaken again on Friday 12th of August 2016 by AWN Consulting at the six identified perimeter locations (SA1 – SA6) around the quarry (see *Figure 1 – Monitoring locations*).

The methodology for the monitoring of asbestos followed *The Health and Safety Executive (HSE) Guidance Asbestos: The Analysts Guide for Sampling, Analysis and Clearance Procedures*, which recommends that sampling and analysis of materials for the presence of asbestos is undertaken to comply with CAWR 2002 ACOPs L27 and L28 when sampling airborne fibres.

The HSE procedure recommends using a known flow rate (ranging from 1-16 L/min) through a filter for a set period of time until 480 litres of air have been sampled. To satisfy the requirement for comparison to the minimum detection limit of 0.01 f/ml, each measurement must be completed on a minimum sample of 480 litres in volume. The fibres can then be enumerated by a UKAS accredited laboratory, in this case, the Institute of Occupational Medicine (IOM).

A decorative graphic consisting of several overlapping, curved, light green and yellow swooshes located in the bottom left corner of the page.

Cork Office
Unit 5, ATS Building,
Carrigaline Industrial Estate,
Carrigaline, Co. Cork.
T: + 353 21 438 7400
F: + 353 21 483 4606

AWN Consulting Limited
Registered in Ireland No. 319812
Directors: F Callaghan, C Dilworth,
T Donnelly, T Hayes, D Kelly, E Porter

Table 1 provides a comprehensive overview of the sampling results from Friday 12th August 2016 and also includes an assessment of the fibre concentrations in relation to the HSA Binding Occupational Exposure Limit.

As with all previous sampling to date the results were again in compliance with the Health and Safety Authority (HSA) Code of Practice (COP) 2011 value of 0.1 f/ml.

2. Dust sampling status

In accordance with the programme outlined in the letter dated 20th June 2016, dust monitoring was again undertaken continuously from Friday 22nd July until Thursday 4th August 2016. The results are presented in Table 2.

Monitoring for PM₁₀ is undertaken at one location (SD1) (see *Figure 1 – Monitoring locations*) using a R&P Partisol®-Plus Sequential Air Sampler (Model 2025). The sampler is a manual air sampling platform which has been designed to meet US EPA Reference Designation (RFPS-1298-127). Approximately 24 m³ of air is sampled daily through a particle size separator, which is contained within the PM₁₀ sampling head. The impactor removes particles with a diameter >10 µg and the remaining particles are collected on pre-weighed 47mm diameter filters. The Partisol® sampler is programmed to automatically replace each sampled filter by a new pre-weighed filter at midnight. This ensures that each filter represents a sampling period of exactly 24 hours. Gravimetric determination is carried out pre- and post-sampling by a UKAS accredited laboratory using a calibrated scientific balance.

As with the previous results, all samples were in compliance with the CAFE Directive 2008/50/EC limit value for PM₁₀ which is 40 µg/ m³ per calendar year or 50 µg/m³ in any 24-hour period (not to be exceeded more than 35 times in a calendar year) (see <http://www.epa.ie/air/quality/standards/>). The monthly average for all samples to date is reported in Table 3.

3. Next available update

Please note that air sampling was again undertaken on Friday 19th of August 2016 following the aforementioned HSE procedure. Due to adverse weather conditions the samples became flooded during sampling resulting in no valid samples available for analysis. As such, there will be no air monitoring results available next week. Air sampling shall again be undertaken on Friday 26th August 2016 with results anticipated during the week starting 5th September 2016.

Dust monitoring has also continued at the site with the next round of dust monitoring results anticipated during the week starting 5th September 2016.

As a result, there will be no results available for reporting during the week starting 29th August 2016.

Yours sincerely,



Teri Hayes
Director AWN Consulting

- cc. *Michael Geaney, A/Director of Services, Water and Environmental Services, Wicklow Co. Council*
David McKeown, Director, Kilsaran International
Jim Fanning, Health and Safety Authority
- encl. *Table 1 – Air Quality Monitoring Programme Results, Ballinclare Quarry, 12 August 2016*
Table 2 - Dust Monitoring Programme Results, Ballinclare Quarry, 04 August 2016
Table 3 - Dust Monitoring Averages, 17 June – 04 August 2016
Figure 1 - Monitoring Locations

Table 1: Air Quality Monitoring Programme Results, Ballinclare Quarry, 12 August 2016


Sample no.	Date	AWN Consultant	Location Description	Total Fibre Concentration (f/ml)	Total Asbestos Fibre Concentration (f/ml)	Analysed by:	HSA Limit Value	Compliant with HSA Binding Occupational Exposure Limit?
AD1	12/08/2016	AC	Section 55 Monitoring SA1 Location	0.00011	<0.00009	IOM	0.1 f/ml	Yes
AD2	12/08/2016	AC	Section 55 Monitoring SA2 Location	<0.00009	<0.00009	IOM	0.1 f/ml	Yes
AD3	12/08/2016	AC	Section 55 Monitoring SA3 Location	0.00019	<0.00009	IOM	0.1 f/ml	Yes
AD4	12/08/2016	AC	Section 55 Monitoring SA4 Location	0.00012	<0.00009	IOM	0.1 f/ml	Yes
AD5	12/08/2016	AC	Section 55 Monitoring SA5 Location	<0.00009	ND<0.00009	IOM	0.1 f/ml	Yes
AD6	12/08/2016	AC	Section 55 Monitoring SA6 Location	0.00011	<0.00009	IOM	0.1 f/ml	Yes

Table 2: Dust Monitoring Programme Results, Ballinclare Quarry, 04 August 2016

Filter Paper ID	Date	PM10 Concentration ($\mu\text{g}/\text{m}^3$)
05474-4	22/07/2016	9
05474-5	23/07/2016	10
05474-6	24/07/2016	8
05474-7	25/07/2016	7
05474-8	26/07/2016	9
05474-9	27/07/2016	5
05474-10	28/07/2016	4
05474-11	29/07/2016	9
05474-12	30/07/2016	6
05474-13	31/07/2016	7
05474-14	01/08/2016	5
05474-15	02/08/2016	8
05474-16	03/08/2016	6
05474-17	04/08/2016	6

Table 3: Dust Monitoring Averages, 17 June – 04 August 2016

1-month Average	8.8 $\mu\text{g}/\text{m}^3$
No. Days >50	0
90.4th %ile	13
No. Days Sampling	42



Legend

Sampling locations/ Type:

■ SA1 - SA6
- Asbestos Sampling Point

■ SD1
- Dust Sampling Point



Do not scale; Indicative Only (NTS)
 0 50 100 Metres

AWN licence no. EN 0007513
 Note: Drawing is for illustrative purposes only
 Source: Kilsaran, flown 28/05/2016

Copyright AWN CONSULTING LIMITED
 All rights reserved. No part of this work
 may be modified or reproduced or copied
 in any form or by means - graphic, electronic
 or mechanical, including photocopying,
 recording, taping or information retrieval
 system, or used for any purpose other than
 its designated purpose, without the written
 permission of AWN Consulting Limited



AWN Consulting Ltd
 The Tecpro Building,
 Clonsaugh Business & Technology Park
 Dublin 17,
 Tel: + 353 1 847 4220
 Fax: + 353 1 847 4257

CLIENT: Kilsaran Ballinclare, Co. Wicklow	PROJECT: Proposed Section 55 Air Monitoring	DRAWN: P.G.	CHECKED: T.H.	APPROVED: T.H.	DATE: 05/07/2016
DRAWING TITLE: Monitoring Locations	Project Ref: TH/16/9020SR01	Figure 1		1	A3
REVISION DESCRIPTION Drawing 05-07-2016				SHEET 1	REV 0